No.	Name of work	Unit	Quantity	Tender rate	
				In figures	In words
2	Stone jelly concrete in surki mortar ..	C.ft.	218		
3	Burnt stone slabs 6" thick dressed and fixed.	Sq.ft.	46		
4	Stone pillars 6" thick dressed and fixed ..	,,	55		
5	Rough stone steening work to well ..	C.yd.	34		
6	Jelly stone filling behind steening work ..	,,	23		
7	Size stone in surki mortar	C.ft.	188		
8	Pointing in surki mortar	Sqr.	3·50		
9	Making notches in beams, etc. ..	Lump sum			
10	Pulleys with iron rod	No.	2		
11	Bailing water	Lump sum			
12	Providing cattle trough near the well in stone	,,			

B. KRISHNASWAMIENGAR,
Executive Engineer.

IRWIN CANAL DIVISION.

Notification dated 12th December 1934.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Irwin Canal Division, up to 1 P.M., on 12th January 1935, for running telephone line from Hosur to Keragode. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of official year 1934-35.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mandya between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for running Telephone Line from Hosur to Keragode " in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Irwin Canal Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates are to be entered both in figures and words.

10. Rates once tendered will on no account be increased afterwards.

11. Tenders stating that the dues in the department may be adjusted towards the earnest money will be rejected.

Estimate of the probable cost of running Telephone Line from Hosur to Keragode on A.K.L. as per accompanying sketch to a distance of $4\frac{1}{2}$ miles.

Sl. No.	Name of materials	Unit	Quantity	Rate	Amount
					Rs. a. p.
1	S. M. Rail 24' long	No.	108		
2	X arm 2 pin D.C.A. with clamps, bolts and nuts, etc., complete	,,	18		
3	Do S. C. A. complete ..	,,	90		
4	Insulator white 2nd grade with pins, wooden, complete	,,	252		
5	Wire, galvanised, No. 8 S.W.G.	lbs.	3,500		

Sl. No.	Name of materials	Unit	Quantity	Rate	Amount
					Rs. a. p.
6	Guy set complete with rod, anchor and wire 7 strand	Set	18		
7	Sundries such as coal tar for rails, soldering materials, binding wire and unforeseen items	L. S.			
8	Wall telephones 5 magnet with necessary equipments such as porous pots, zinc rods, L.L. cells, battery box, foot board, lightning arrestors, etc., complete (one at Hosur and one at Keragode)	No.	2		
9	Wiring materials	L. S.			
10	Grounding materials	No.	3		
11	Jungle clearing and compensation	L. S.			
12	(*a*) Labour charges for digging pits, erecting poles and fixing X arms	No.	108		
	(*b*) Stringing Telephone Wire	Miles	9		
	(*c*) Tarring poles	No.	108		
	(*d*) Installing wiring the instrument and grounding	L. S.			
13	Carting the materials	,,			

C. T. NARASIMHA IYENGAR,
Executive Engineer.

HASSAN DIVISION.

Notification dated 20th December 1934.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 3 P.M. on 25th January 1935, for Restoring Chickagenegere, Hongekatte Minor Tank Register No. 582 of Hassan Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a desposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Chickagenegere, Hongekatte Minor Tank Register No. 582 of Hassan Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent of contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer, will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for Restoring Chickagenagere Hongekatte Minor Tank Register No. 582 of Hassan Taluk.

No.	Items of work	Unit	Quantity
	Bund.		
1	Earth work raising the bund with consolidation	C.yd.	4,810
2	Turfing front and rear slopes	S.yd.	6,047
3	Providing and fixing new grade stones including cutting figures	Each	14
4	Index stones	,,	14
5	Register No. of stone	,,	1
6	Register B. M. No. stone	,,	2
7	Removing jungle on top	Grade	13
		Lump sum	
	Sluice.		
1	Cut opening the bund and refilling with consolidation ..	C.yd.	168
2	Concrete in surki mortar	S.ft.	347
3	Size stone in surki mortar	C.ft.	452
4	Burnt stone slabs $4\frac{1}{2}$" to 6" thick dressed and fixed	S.ft.	102
5	Providing 6" diameter C. I. pipe (carting and fixing charges to be tendered)	R.ft.	36
6	Drilling holes in orifice and the other slabs	Each	4
7	Cement pointing to slabs	Sqr.	·32
8	Plastering with surki mortar	,,	1·62
9	Providing jelly or teakwood plug and read and locking arrangements	Each	1
10	Cutting draft channel	C.yd.	125
11	Rough stone revetment	,,	11
	Rough stone Waste Weir.		
1	Earth work excavation of body	C.yd.	6
2	Rough stone body wall	,,	6
3	Clearing the draft and approach	Lump sum	

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE DEPUTY DIRECTOR OF PUBLIC INSTRUCTION, BANGALORE DIVISION.

Notification No. A1. 2180-642 *of* 1932-33, *dated 26th December* 1934.

The date of auction of the unserviceable articles of this Office which had been fixed for the 22nd December 1934 at 3 P.M. (*Vide* notification published on page 1688, Part VI of the *Mysore Gazette*, dated 20th December 1934), is postponed to 10th January 1935 at 3 P.M., as no bidder turned up on the 22nd December 1934.

S. P. CHINNAPPA,
Deputy Director.

OFFICE OF THE SUPERINTENDENT, GOVERNMENT PRINTING IN MYSORE, BANGALORE.

Abstract Notice, dated 29th December 1934.

The attention of the public is invited to the detailed notice, dated the 12th December 1934, published on page 1688 of Part VI of the *Mysore Gazette*, dated the 20th December 1934, regarding the sale of unserviceable articles at the Government Central Press, Bangalore, on Wednesday the 16th January 1935 at 3 P.M.

B. SRINIVASA IYENGAR,
Superintendent.